BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/11/2020-21 Date: 20.02.2021

Indet No: BBMP/2020-21/OW/WORK_INDENT46979

SCHEDULE -B

Name of Work: Providing missing slabs and desilting of drains in ward jurisdiction in ward no 16 Jalahalli

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	1144.84	Removing and refixing stone slabs of drains and pointing in CM (1:3)	Sqm	111.80	Rupees One Hundred Eleven And Paise Eighty Only
2	489.40	KSRRB 300-3. Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification	Cum	233.20	Rupees Two Hundred Thirty Three And Paise Twenty Only
3	616.45	Providing & laying precast drain cover slab of 100 mm thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(0.90 x 0.60 x 0.10) (Approved Data rate)	Cum	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP